

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon
 (County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------------|---------------|-----------|
| 1. Public Land Survey | T <u>53</u> N | R <u>38</u> W | <u>J9</u> |
| | T <u>53</u> N | R <u>38</u> W | <u>J8</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 17 2000

I, Stephan J. Szyszko, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|----|---|----|---|----|---|----|---|----|---|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

- A. Description of original monument and accessories and/or subsequent restoration:
 (J9) Quarter corner common to Sections 23-26. Established in 1846 by Higgins and Hubbard. "West corrected...39.92 set 1/4 Sec. post, Hemlock 14 N55W 18, Hemlock 24 SSE 80...79.85 Section corner". Found no subsequent record.
 (J8) Center of Section 23. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (J9) The original post and accessories were not recovered. Reestablished the corner by single proportionate measurement to the original record between Section corners east and west. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. This mile is substantially shorter than the record, being 76.45 chains in length. From the corner monumented, I found an old wood post, placed by persons unknown, and a metal location poster dated 1971, marked "approx. corner", S59W, 232.5 ft. distant.
 (J8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners and monumented it with a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (J9) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 10" Y. Birch N85W 9.3' "1/4S NBT" 15" Cedar N38W 27.3' do 16" Cedar N88E 14.0' do 11" Cedar S41E 29.3' do Placed squared cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze. | (J8) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 18" Cedar N19W 63.9' "C1/4 BT" 8" Sugar N69E 15.9' do 9" Cedar S28E 51.8' do 12" Hemlock S10W 28.1' do Placed a squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze. |
|---|--|



Signed by Stephan J. Szyszko Date 5/15/00
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division