

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>17</u> N. R. <u>7</u> W.	A-6; C-5; C-6
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 17, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-6 Restored corner in line with old fence to W (W of county road) & two old posts still standing in marsh & beaver pond between corner & existing relocated county road to W. Quarter line fence fits eighth line fences on split of section line, half mile N & S. The departure of the ¼ corner was established on average line of road & R.O.W. fences to N & S which fits found concrete monument on section line per "Plat of Maddern Subdivision."
- C-5 Recovered iron in monument box that fits three McClung witnesses.
- C-6 Recovered 7/8" iron rod that fits McClung witness.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6	C-5	C-6
Set DNR cap on 1"x13' pipe in 5' of water	Found ½"x½" iron in mon. box NW'ly corner brick house porch found	Found 7/8" iron rod in N-S blacktop road
Set 1"x4' pipe & cedar post N00°46'E 342.0	36" Cottonwood S50°W 50.81	P. Pole N25°E 96.86 Tel. Pole S60°W 55.03
Found concrete Plat mon. & Cedar post S00°15'W 257.4		Set ced. post w/loc. tag Due E 33' Ctr. N-S rd. Due W 7' Ctr. gravel rd. W Due S 12'


SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ ORIENT TOWNSHIP
OSCEOLA COUNTY