

**SURVEY &
REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

DEC 1 6 1996

COMMISSION

For corners in

<u>Osceola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T17N RW</u>	<u>D-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew A. McClung
10 Oct 1996

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung, in a field survey on 09-20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor Orson Lyons on 6 January 1837 Set wood post at 39.80 chains from East.

Sugar 7" S60 1/2W 11 lks.
Beech 11" N77 1/2E 43 lks.

From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Excavated with back hoe to depth of 36". Found tile and cinders. Found no other evidence of corner. Placed Osceola County Monument over tile 6" below surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D-5. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.
6" Elm N06W 41.2 feet.
14" Thornapple South 87.6 feet.
12" Cedar S74E 131.6 feet.
9" Cedar of 2 twisted trees in clump of 4 S60E 107.6 feet.



Signed by *Matthew A. McClung*
Surveyor's Michigan License No. 13037

Date September 20, 1996

OSCEOLA COUNTY
REGISTER OF DEEDS

96 NOV -7 AM 11:57

Marcy Crawford

thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a 1/2" iron bars were added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been entered in the County Surveyor records.

Orient Township Record Book; Front Pages, Page 2.

SURVEY &
REMONUMENTATION

DEC 1 6 1996

COMMISSION