

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Osceola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>6</u> T <u>17N</u> R <u>8W</u>	<u>6</u>
	S <u>6</u> T <u>17N</u> R <u>8W</u>	<u>9</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Num

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on Jan. 22 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- |  |  |
|--|--|
| <u>6</u> - Lakestate Sur. & Eng. - File #4858-87-<br>Clinton Cole - 1987 - Survey marker set | <u>9</u> - Rec. Survey L. -326 P. 155<br>M. McClung RLS #13037<br>1976 - Set 3/4" rod with cap<br>- Rec. Survey L.515 P. 18 - G. J. Gray<br>1989 - Fnd. iron |
|--|--|



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- |   |  |
|---|--|
| <u>6</u> - NE 1/16 Cor. Sec. 6. FND. PS Cap #17615<br>on 1/2" rebar set in concrete<br>0.97'S & 0.72'W of calc. position at N. Side<br>4" Cedar anchor post for fence to S.<br>Monument accepted as best available<br>evidence of the position of corner. | <u>9</u> - CE 1/16 Cor. Sec. 6 - Previous iron obliterated<br>from pond construction.<br>Set 2" AC on 5/8" x 34" rebar per<br>standard BLM procedure on E. Side of Pond. |
|---|--|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| <u>6</u> - P.S. Cap #17615 on 1/2" rebar in concrete<br>East 24.20' set N&T N. side 8" Elm<br>N58°E 52.33' Set N&T NW side 13" Cedar<br>N2°W 68.90' Set N&T W. side 11" Cedar<br>S80°W 13.06' Set N&T S. side 7" Ash<br>Set Blue Carsonite post 1' NW | <u>9</u> - 2" Alum. Cap on 5/8" x 34" rebar<br>S51°W 73.5' NE corner siding on frame shed<br>N51°W 116.35' Set N&T SW side 8" Cherry<br>N1°W 127.15' Set N&T W. side 8" R. Pine<br>N65°E 59.00' Set N&T N. side 14" R. Pine<br>S23°E 133.3' to NE Cor. siding of Hse. addition<br>Set Blue Carsonite post 1'NW |
|---|--|

Signed by Craig W. McVean  
 Surveyor's Michigan License No. 39088

Date 4/20/1998