

SURVEY & REMONUMENTATION

DEC 13 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

For corners in <u>Osceola</u>	Located in:	Corner Code#	
1. Public Land Survey	T 17 N	R 8 W	H-13
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S T	R	
	S T	R	
3. Miscellaneous Property in Sec.	S T	R	
	S T	R	
4. Lot No. _____ Recorded Plat _____			
5. Private Claims _____			

OSCEOLA COUNTY
 REGISTER OF DEEDS
 00 MAY -5 PM 2:50
Francis Campbell

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on March 22, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

H-13 - S. 1/4 Corner Sec. 34, T17N, R8W

A. Description of original monument and accessories and/or subsequent restoration:

1848 - O. Lyon, G.L.O.

- #1 - 6" Tamarack N68°E 33 Links
- #2 - 6" Tamarack N56°W 23 Links

1891-1904 - A.O. Temple

- Remonumentation of T17N, R8W
- "Identified by Stake"
- Set 3" Clay Tile.
- #3 - 44" Elm N65 1/2°W 378 Links

1906 - F. Trumbull Co. Sur.

- From Mecosta Co. Sur. Notes in Sec. 3, of T16N, R8W
- #4 - Distance East to Sec. Cor. 2576.64'
- #5 - Distance West to Sec. Cor. 2621.52'

1995 - R. L. Wetherell, LS 24624

- L.C.R.C. - Liber 03, Pg. 122.
- "Tile & Iron".
- #6 - 9" Maple N83°W 167.57'
- #7 - 1/2" Capped Iron S67°W 347.27'

APPROVED LAND CORNER
 P. 135 OF 1890
 OSCEOLA COUNTY

R. L. W.
4-20-2000

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1/2" Iron Rod in center of 3" clay tile. Corner is in old beaver flooding area.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Measured 2612.26', #5 Measured 2653.76', #6 Found in good condition, #7 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 1" x 30" pipe with Osceola County Remon Cap over the 1/2" Iron Rod, and is accepted as a careful and faithful perpetuation of the position of the original corner.

- 10" Maple N83°W 167.57' (60d spike S. side) #6
- 1/2" Iron with cap (LS24624) S67°W 347.27'
- Osceola County Remon Iron West 2653.76' (Sec. Cor. common to Sec. 33 & 34)
- 3/4" Iron in Monument Box - East 2612.26' (Sec. Cor. common to Sec. 34 & 35)



Signed by Robert L. Wetherell
 Surveyor's Michigan License No. 24624

Date April 25, 2000