

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 17 ^{N.} R. 9 ^{W.}	J-1
2. PROPERTY CONTROLLING IN SECTION 1 _____	T. 17 ^{N.} R. 9 ^{W.}	15; 16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} R. _____ ^{E.}	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 6, 19 77, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- J-1 Set corner by proportionate measurement, midpoint on line, between section corners for Section 2. No previous corner.
- 15 Set by standard survey procedure for subdivision of sections, midpoint on line; between section and ¼ corners.
- 16 Found corner as previously established in local survey of Section 1 by Lake State Surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1	15	16
Set DNR monument & cedar post	Set 5/8"x40" rod/cap & cedar post	Fd. ½" rod w/RLS cap
6" Maple N35°E 13.3	8" R. Oak N22°W 58.6	5" W. Pine N50°E 41.2
2" W. Oak S55°E 18.7	11" Tw. R. Oak S15°E 19.2	9" W. Pine S03°W 28.4
E-W random Due N 5.3	6 US-10 Due N 145	4" Conc. monument & cedar post Due N 33'
S¼ Sec. 35 T17N-R9W Due W 20.9	Fd. 3/4"x18" Iron Rod Due W 48.65	

SIGNED BY Kenneth J. Ostling
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

DATE 12



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____
 HERSEY TOWNSHIP
 OSCEOLA COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET