

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Osceola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
2. Property Controlling in Section	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S <u>1</u> T17W R 9W	<u>9</u>
	S <u>1</u> T17N R 9W	<u>2</u>
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on Jan. 20 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 9 - Lake State Survey & Eng. - File #2379-75
 C. Cole - 1975 - Set Iron, L. 325, P. 604,
 Osceola Co. records.
- 2 - None.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 9 - C-E 1/16 Corner - FND. PS Cap 17615
 on 1/2" x 18" Rebar per Lakestate Sur. -
 Fits calculated position closely.
 Monument accepted as the best available
 evidence of the position of the corner.
- 2 - E 1/16 Corner on N. Line of Sec. 1
 - Set 2" A.C. on 5/8" x 34" Rebar per
 standard BLM Procedure. Down E-W
 fence remains are 22' ± N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 9 - Replaced capped 1/2" Rebar with 2" Alum. Cap on
 5/8" x 34" Rebar at E. Side FND. Cedar Post
 N86°E 91.95' Set N&T N. Side 4" W. Oak
 N34°W 25.59' Set N&T N. Side 9" W. Oak
 S17°W 19.16' Set N&T W. Side 4" R. Maple
 S31°E 8.45' Set N&T W. Side 7" R. Oak
 Set Blue Carsonite post 1'E.
- 2 - 2" Alum. Cap on 5/8" x 34" Rebar
 S4°E 36.82' Set N&T E. Side 11" R. Maple
 S33°E 29.96' Set N&T E. Side 12" R. Maple
 S65°E 27.60' Set N&T SW. Side 18" R. Oak
 N53°E 10.34' Set N&T SE Side 19" Tri. R. Oak
 Set Blue Carsonite post 1' SE.

Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 4/20/1998