

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T _____ R _____
 T _____ R _____

2. Property Controlling S 1 T 17N R 9W _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on Jan. 21, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

11 - None.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

11 - SW 1/16 Corner, Sec. 1
 - Set 2" A.C. on 5/8" x 34" Rebar
 per Standard BLM Procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

11 - 2" Alum. Cap on 5/8" x 34" rebar.
 S22°W 11.65' set N&T E. side 4" R. Maple
 S54°W 19.98' set N&T NW side 4" R. Oak
 S80°W 15.08' set n&T N. side 5" R. Oak
 N28°W 22.25' set N&T E. side 2" R. Oak
 Set Blue Carsonite post 1' NW



Signed by Craig W. McVean
 Surveyor's Michigan License No. _____ 39088

Date 4/20/1998