

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Osceola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>3</u> T <u>17N</u> R <u>9W</u>	<u>9</u>
	S <u>3</u> T <u>17N</u> R <u>9W</u>	<u>13</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on Jan. 15 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3	●	2		1	
3									●				
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

9 - None. 13 - None.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>9</u> - C-E 1/16 Corner, Sec. 3 - Set 2" AC on 5/8" x 34" rebar per standard BLM procedure. N-S barb wire in trees and posts 142' E.	<u>13</u> - SE 1/16 Corner Sec. 3 - Set 2" AC on 5/8" x 34" rebar per standard BLM procedure. E-W barb wire fence 50.8' N. E-W fence intersects barb wire fence bearing N. at post N9° E 51.1'.
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>9</u> - 2" Alum. Cap on 5/8" x 34" rebar S48°E 36.65' set N&T N. side 4" R. Maple N55°E 31.63' set N&T SE side 20" R. Maple N8°E 70.92' set N&T SE side 3" R. Maple S63°W 31.84' set N&T NW side 4" R. Maple Set blue carsonite post 1'E	<u>13</u> - 2" Alum. Cap on 5/8" x 34" rebar N12°E 26.38' set N&T W. side 5" R. Oak N53°W 29.58' set N&T SW side 4" R. Maple S63°W 15.53' set N&T S. side 6" R. Oak N88°E 34.62' set N&T N. side 11" R. Maple (clp. of 4) Set blue carsonite post 1'NE
--	---

Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 4/20/1998