

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Osceola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>9W</u>	<u>M-2</u>
	T <u>17N</u> R <u>8W</u>	<u>A-2</u>
2. Property Controlling in Section	T ___ R ___ S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on Nov. 3 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-2 & M-2 - GLO - Set 1/4 Post - J. Hodgson - Oct. 30, 1837
W. Oak 8" S42°W 17L., Beech 10" N64°W 40L.
- Large Osceola Bk. 1, P. 503 - F. Trumbull - 1900's +
FND. Stake - Set Tile Mon. - Pine Stp. 18" N26°E 16.5L.,
Pine Stp. 18" N81°W 36L.
- LCRC L.1, P. 377 - FND. Tile & Rod - Set Brass Cap -
M. McClung - 1975 - 4" W. Oak N3°W 26.0', 10" R. Oak
53°W 52.7', 2" Maple N10°W 5.6'
- Rec. Survey L. 515, P. 18 - G.J. Gray - FND. Brass Cap - 1989



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-2 & M-2 - 1/4 Corner Common to Sec. 1, T17N, R9W and Sec. 6, T17N, R8W - FND. 3/4" Iron Rod in Tan Vit. Tile with 2 1/2" Osceola Co. Brass Cap leaning loosely almost over center of Iron & Tile. Centered top of brass cap over Tile Mon. Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-2 & M-2 - 2 1/2" Osceola Co. Brass Cap on 1" Pipe centered and leaning Nly over 3/4" Iron Rod in Tile. Built Ring of Stone
Set Carsonite Post 1.2' NW
N10°W 5.55' to Set N&T in W. Side 7" R. Maple scribed 'XBT' (MM)
North 25.90' to Set N&T in E. Side 10" W. Oak scribed 'XBT' (MM)
N86°W 27.87' to Set N&T in N. Side 4" W. Oak scribed 'XBT'
S23°W 53.25' to Set N&T in E. Side 14" B. Oak scribed 'XBT'
N65°E 15.89' to Set N&T in N. Side 5" R. Maple scribed 'XBT'

Signed by Craig W. McVean
Surveyor's Michigan License No. 39088

Date 4/20/1998