

SURVEY & REMONUMENTATION

FEB 12 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

Osceola

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-----------|---|-----------|-------|
| 1. Public Land Survey | T | <u>17</u> | R | <u>9W</u> | H-1 |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

6 Nov 1997
Matthew M. Clung

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung in a field survey on Oct 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found M.D.N.R. Monument with Cedar Post. This corner is recorded as the N 1/4 Corner of Section 3 of Hersey Township. (State Project No. 75-44.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H-1. M.D.N.R. Monument with Cedar Post.
Treated 10' High Fence Post N22W 37.20 feet.
18" Maple with nail S25W 49.25 feet O.B.T.
10" Double W Oak N21W 66.94 feet O.B.T.
12" W. Oak with nail N42E 44.7 feet O.B.T.
20" R. Oak N78W 130.7 feet
19.6' West to H-13 T19N-R9W, Cedar Township.



Signed by *Matthew M. Clung*
Surveyor's Michigan License No. 13037

Date Oct 21, 1997

SURVEY &
REMONUMENTATION

FEB 12 1998

SECTION

OSCEOLA COUNTY
REGISTER OF DEEDS

97 DEC 11 PM 2:10

Nancy Crawford

By Ostling, dated Dec. 16, 1977.
L.C.R.C. Liber 2, Page 6.
Set Corner Midpoint on line
between Corners Section 3.
9" W. Oak N45E 43.9'
13" Maple S25W 48.6
E & W random Due N 1.9
S. 1/4 Sec. 34 T18N-R9W
Due West 19.6

By. Fokens, Dated April 26, 1993.
L.C.R.C. Liber 3, Page 62
N1/4 Cor. Sec. 3 found M.D.N.R. 1" pipe
W/Cap
W. 19.70' S1/4 cor. Sec. 34, T18N-R9W,
Fd. Standard DNR 1" pipe W/Cap.
N08W 65.35' Nail & LSC Tag #21567 in
S. face W/blaze Twin 10" R. Oak.
S25W 49.39' - Nail & LSC tag #21567 in SW
face w/blaze 12" Maple. N50E 44.52' -
Nail & LSC Tag #21567 in SE face
W/Blaze 18" R. Oak.

PA 132, Liber 562, Pages 654,
655, and 656. by Jan Fokens.
No Witnesses shown.

Map of State protect No. 75-44