

FEB 16 1999

OSCEOLA COUNTY REGISTER OF DEEDS

98 DEC -1 PH 4:58

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola
(County)

Located In:

Corner Code #

- 1. Public Land Survey T17N R9W I-4
- T___ R___
- T___ R___
- T___ R___
- 2. Property Controlling in Section S___ T___ R___
- S___ T___ R___
- 3. Miscellaneous Property in Sec. S___ T___ R___
- S___ T___ R___

James Crawford

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew A. McClung
12 Nov. 1998

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Matthew McClung in a field survey on 11-2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
The original corner was set by deputy surveyor John Hodgson 10 June 1838.
Set wood post 40.00 chains from South.
Beech 7" S16E 8 lks.
Beech 7" S72W 22 lks..

From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" Aluminum DNR Cap P.S. 39088, in center of white clay tile.
Distance from I-4 to I-3 = 2636.408.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner I-4. 2" aluminum DNR Cap on 5/8" rod 40" long.
Fence post N15E 2.62 feet.
Fence Post S02E 14.23 feet.
Fence post S01E 31.22 feet.
Fence post N02E 18.95 feet.
Centerline U. S. 10 North 547.67 feet.



Signed by Matthew A. McClung
Surveyor's Michigan License No. 13037

Date 1 Dec. 1998