

FEB 16 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Osceola</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>17</u> N <u>R</u> L <u>W</u>	<u>G-8</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County
Matthew McClung
12 Nov. 1998

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung, in a field survey on 11-2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor John Hodgson on 10 June 1838. Set wood post 40.00 chains from South.

- Beech 7" N34W 14 lks.
- Beech 9" S85E 18 lks.

From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" capped rod, #24624, at surface. Excavated around iron 10 to 12" below surface, into subsoil, and found no other evidence of the corner. Placed Osceola County Monument over capped iron, in original position of capped iron. Corner is in fence line to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G-8, is an Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.

- 18" Pine w/nail S38W 20.15 feet. O.B.T.
- Power Pole w/nail S82E 30.2 feet. O.B.P.
- 18" Pine S80W 22.6 feet. O.B.T.
- 5" S. Pine S82E 5.25 feet.



Signed by Matthew McClung
Surveyor's Michigan License No. 13037

Date 1 Dec 1998

GUTHRY &
REINFORCEMENT

FEB 16 1999

SECTION

OSCEOLA COUNTY
REGISTER OF DEEDS

98 DEC -1 PH 4:58

Nancy Crawford

thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a 1/2" iron bars were added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 1 of the townships have been recorded in the County Survey records.

Act 132, Liber 474, page 344.
14" S. Pine S24W 20.06'
Power Pole East 30.02'
14" S. Pine S70W 22.67'
Distance G-8 to G-7 = 2641.6'