

FEB 16 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Osceola

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 17 N R 10 W G-10
 T ___ R ___
 T ___ R ___
 T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
12 Dec 1998

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Matthew McClung in a field survey on 9-12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 The original corner was set by deputy surveyor John Hodgson on 10 June 1838. Set wood post 40.00 chains from South.
 Beech 10" N84E 38lks.
 Beech 7" N34E 11 lks.
 From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Excavated to 10" below surface in Monument box, and found 2" angle iron 1/2" thick.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner G-10. Corner is 2" angle iron 1/2" thick.
- 40" Elm Stump West 53.7 feet O.B.P.
- 6" treated fence post East 40.6 feet.
- 4" treated fence post N40E 66.3 feet.
- West most Elm in clump of 3 N80E 35.3 feet.
- 14" Maple N18E 132.3 feet.



Signed by *Matthew McClung*
 Surveyor's Michigan License No. 13037

Date 1 Dec 1998

SURVEY &
RECORDS DIVISION

FEB 18 1999

SECTION

OSCEOLA COUNTY
REGISTER OF DEEDS

98 DEC -1 PM 4:58

Nancy Crawford

thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a 1/2" iron bars were added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been recorded in the County Survey records.

Act 74, Liber 2, page 344 by Gray.
Found steel rod in Mon. box.
SW Cor. of Culvert Az 230 35.05'
Fence Cor. post. Az 90 41.05'
40" dead Elm Az 270 52.40'

Act. 132, Liber 316, Page 542.
Found iron.
Same Witnesses Act 74.