

**SURVEY &
REMONUMENTATION**

AUG 27 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Osceola

(County)

Located In:

Corner Code-#

18N 7W

E-5

- | | | | |
|---------------------------------------|---|---|-------|
| 1. Public Land Survey | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling
in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous
Property in Sec. | S | T | R |
| | S | T | R |

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
25 July 1996

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Matthew McClung July 8, 1996

I, _____, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor Orson Lyons on July 1, 1847. Set temp. wood post 80.00 chains from the South.

Hemlock 16" S64 $\frac{1}{2}$ W 11 lks.

Hemlock 18" S36E 10 lks.

I have shown 2 LCRC certificates; Liber 2, Page 18; Liber 2, Page 139.

Sylvan Township Record Book Pages 36 and 37 also in front pages of book, page 5.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe 3' North of centerline in East and West road 5' below road surface. Excavated to 15" and found crockery around 1" pipe. Placed Osceola County Monument over center of 1" pipe 6" below road surface. Corner is in North and South fence row.

Matthew McClung
96 AUG -7 PM 4:30
OSCEOLA COUNTY
REGISTER OF DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E-5. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.

NW Corner of House S25E 112.00 feet O.B.P.

24" Cherry N46W 30.45 O.B.P.

Power Pole N4E 40.55 feet.

6" Maple S65E 76.60 feet.



Signed by *Matthew McClung*

Date July 8, 1996

Surveyor's Michigan License No. 13037