

**SURVEY & REMONUMENTATION**

NOV 15 1994

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Osceola  
 (County)

Located In: Corner Code #

1. Public Land Survey	T 18N R 7W	F-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

APPROVED LAND CORNER  
 P.A. 345 OF 1990  
 Osceola County

*Matthew McClung*  
 October 11, 1994

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Matthew McClung in a field survey on October 3, 19 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:


The original corner was set by deputy surveyor Orson Lyons on 14 April 1847. Set wood post 39.875 chains from East.  
 Beech 9" S42E 19 lks.  
 Beech 11" S82W 26 lks.

The corner has an LCRC Liber 3, page 14 by McClung

Front pages of Township Book 3rd page from index.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rod and cap # 13037, 4" below road surface. Excavated to 16" and found 1 1/4" pipe. The rod is driven into the pipe. Bent rod to the west, and placed Osceola County Monument over pipe, 5" below road surface.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G-11. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.  
 4" N Pine N30E 35.95 feet. O.B.T.  
 2" Elm North 39.5 feet. O.B.T.  
 14" Pear N40W 74.4 feet. O.B.T.  
 Power Pole S70E 125.10 feet.  
 As called in Township Book Elm 6" S1W 62.3 feet. O.B.T.

*Nancy Crawford*  
 OSCEOLA COUNTY REGISTER OF DEEDS  
 94 NOV -4 PM 2:47

Signed by Matthew McClung

Date October 3, 1994

Surveyor's Michigan License No. 13037