

**SURVEY & REMONUMENTATION**

AUG 23 1995

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**

<u>Osceola</u> <small>(County)</small>	Located In:	Corner Code #
	18N 7W	I-5
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County

*29 June 1995*  
*Matthew McClung*

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Matthew McClung, in a field survey on June 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
The original corner was set by deputy surveyor Orson Lyons on 1 July 1848. Set wood post 80 chains from South  
Beech 11" N54E 47 lks.  
Beech 12" S57W 25 lks.

I have shown 1 LCRC Act 74 certificates.  
I have shown 1 Act 132 survey certificates.  
I have added copies of pages 72 and 73 of US Government Surveys.  
I have shown plat of Wild Life Shores Subdivision.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found Plat Monument in Plat of Wild Life Shores.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Corner I-5. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.  
18" Beech S72E 12.95 feet.  
SE corner of House N74W 28.06 feet  
2" Spruce S16E 4.39 feet.  
14" Hemlock N44W 37.94 feet. O.B.T.  
11" Maple N74E 17.56 feet, Blazed O.B.T.

*Yancy Daugherty*  
**95 JUL - 6 AM 10:40**  
**OSCEOLA COUNTY REGISTER OF DEEDS**

Signed by Matthew McClung Date June 12, 1995  
Surveyor's Michigan License No. 13037

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 25, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983