

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Osceola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>8W</u>	<u>A4</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on June, 19 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-4 - GLO - Set 1/4 Post - J. Hodgson - 1837
 Maple 6" S45°W 8L
 Beech 7" N12°W 51L

- From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a iron bar or pipe was added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been entered in the County Surveyor's records.
- Co. Surveyor - Cedar Twp. F.B. P. 29 - Distance N&S-1904±

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4 -Standard 1/4 Corner common to Sec. 12, T18N, R9W & Sec. 7, T18N, R8W - FND. Bent 1/2 Iron Rod in 3" Dia. Vit. clay tile Mon. in N-S. fence line remains. Mon. consistant with 1900's. Remon. and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4 - Straighten 1/2" rod & Drive 1" x 4' long iron pipe w/4" MDNR Alum. Cap over 1/2" Iron in center tile Mon. Built ring of stone. Set Blue carsonite post 1' ± N.
 N78°E 48.86' to N&T in N. Side 11" Triple R. Maple
 N34°W 34.82' to N&T in SW Side 12" R. Maple in clump
 N81°W 35.05' to N&T in N Side 15" Twin R. Oak
 S30°W 57.16' to N&T in NW Side 13" Twin R. Oak
 Note: All BT's scribed 'XBT'

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 10/14/1998