NOV 1 6 1998

SECTION.

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Filing Requirement of Act 74, Mich. P.A. 1970	
For corners in	APPROVED LAND CORNER
Osceola Located In: Corner Code #	P.A. 345 OF 1990 Osceola County
1. Public Land Survey T 18N R 8W A-3 V	Markey Myling
2. Property Controlling S T /8N R 9 W M-3 in Section S T R  3. Miscellaneous S T R Property in Sec. S T R	Register of Deeds Stamp & File Num
4. Lot No, Recorded Plat	
T. LOUING, Necolded Flat	ABCDEFGHIJKLM
5. Private Claims	3 2 1 1 2 1 1 2 1 1 1 2 1 1 1 1 2 1 1 1 1 1 2 1
I, Craig W. McVean, in a field survey on April 7, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:	5 6 -18 -17 -16 -15 -14 -13 7 8 -19 -20 -21 -22 -23 -24 9 10 -30 -29 -28 -27 -26 -25 11
NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.	12 31 32 33 34 35 36
A. Description of original monument and accessories and/or subsequent restoration:	
A-3 - GLO - Set Post, T18N,R 9W - J. Hodgson - 1837  Beech 12" S20°W 30L.  Beech 7" N37°W 12L.  GLO - Orson Lyon - 1847 - Sub. T18N, R8W - Correct E. from standard post  Beech 7" N81 1/2°E 7L.  Beech 10" S34 1/2°E 28.5L.  GLO Examination - A.P. Brewer - 1854 - Started here & surveyed West.  From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a iron bar or pipe was added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been entered in the County Surver records.  Osceola Co Cedar F.B., P. 29 - Distance W&S - 1904 +	
B. Description of corner evidence found and/or method applied in restoring or reestablishing	g corner:
A3 - Standard Sec. Corner Common to Sec. 1 & 12, T18N, R9W and Sec. 6 & 7, T18N, R8W - FND. Bent 1/2" x 4' Long Iron Rod in 3" Vit. Tile Monument with cinders. Ancient fence corner for fence remains S, E & W is 33' S. Monument accepted as the best available evidence of the position of the original corner.	
C. Description of monument for corner and accessories established to perpetuate locating th	e position of the corner:
A3 - Replace Bent 1/2" Iron Rod with 4" DNR Alum. Cap on 1" x 35" Galv. Iron Pipe drove into center of tile Mon. Reset 1/2" Iron Rod on W. Side of tile as memorial. Built Ring of Stone. Set Blue Carsonite Post 1' N. N72°W 103.92' to N&T in S. Side 12" R. Pine scribed 'XBT' N32°W 23.53' to N&T in NE Side 5" R. Maple scribed 'XBT' N23°E 25.55' to N&T in SE Side 3" R. Maple scribed 'XBT' S37°E 27.26' to N&T in SW Side 8" R. Oak scribed 'XBT' S17°W 36.10' to N&T in W. Side 5" R. Oak scribed 'XBT'  S17°W 36.10' to N&T in W. Side 5" R. Oak scribed 'XBT'	McVEAN * PROFESSIONAL SURVEYOR O
Signed by Prace W. Mellan	Date 10/14/1998
Surveyor's Michigan License No. 39088	