

SURVEY & REMONUMENTATION

SEP 15 1994

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola
(County)

Located in:

Corner Code #

- | | | | |
|------------------------------------|--------------------------|------------|--|
| 1. Public Land Survey | T <u>18N</u> R <u>8W</u> | <u>E-4</u> | |
| | T _____ R _____ | _____ | |
| | T _____ R _____ | _____ | |
| | T _____ R _____ | _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | |
| | S _____ T _____ R _____ | _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ | |
| | S _____ T _____ R _____ | _____ | |

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew A. McClung
26 July 1994

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Matthew McClung a field surveyor on June 12, 19 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor Orson Lyon on April 14, 1847. Set wood post 40.00 chains from the South.
Beech 12" S15E 24 lks.
Beech 18" N52W 60 lks.

From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar in road 0.25' below road surface, bar is 1.75' long. Found 3" glazed tile 1.9' below road surface. Top of bar was 0.4' west and 0.3" south of tile center. Set Osceola County Monument inside tile, 5" below road surface, in center of road.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E-4. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.
Power Pole No. 106C N88E 59.24 feet.
9" R. Oak S30E 41.15 feet.
12" R. Oak S58W 40.40 feet.
10" Cherry N55W 39.05 feet.

Signed by Matthew A. McClung Date June 12, 1994
Surveyor's Michigan License No. 13037

OSCEOLA COUNTY
REGISTER OF DEEDS

94 AUG 19 PM 3:29

Nancy Crawford

thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a 1/2" iron bars were added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been recorded in the County records.