

FEB 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

For corners in Osceola	Located in:	Corner Code#	
1. Public Land Survey	T 18N	R 8W	E-6
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	T	R	
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R
4. Lot No. _____ Recorded Plat _____			
5. Private Claims _____			

OSCEOLA COUNTY
 REGISTER OF DEEDS
 99 NOV 19 PM 12:09
Nancy Campbell

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on October 5, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

E-6 - 1/4 Corner common to Sections 16 & 17, T18N, R8W, Osceola Co., Mi.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|---|---|--|
| <p><u>1848 - O. Lyon, G.L.O.</u>
 #1 - 15" Hemlock S37°E 19 Links
 #2 - 16" Hemlock N52°W 15 Links</p> <p><u>1891 - 1904 - Temple/Trumbull</u>
 Osceola Twp., (T18N, R8W) had a remonumentation program.
 3" Clay Tiles were set.</p> | <p><u>Undated Osceola Twp., Book</u>
 Page 3 (Front)
 #3 - 10" Maple S58 1/2°W 48.8'
 #4 - Post S84°E 33'</p> | <p><u>1994 - R.L. Wetherell, LS 24624</u>
 Survey recorded Liber 583, Pg. 460
 #5 - 18" Maple S9°E 73.82'
 #6 - 8" Maple S36°W 58.43'
 #7 - 10" Maple N74°W 25.33'
 #8 - 4" Maple N26°E 73.89'</p> |
|---|---|--|

B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:

I found a 1/2" rod in 3" Clay tile 4 inches below road surface. Corner is in the center of North and South road and in line with fence to West and old tree line east.

Condition of the accessories are as follows: #1 gone, #2 Gone, #3 Found remains of stump, #4 Gone, #5 Found in good condition, #6 Found in good condition #7 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I place a 1" x 18" pipe with Osceola County Remon Cap in the center of Tile and is accepted as a careful and faithful reestablishment of the position of the original corner.

20" Maple S10°E 73.41' (60d spike in W. side) #5
 13" Maple N74°W 25.35' (60d spike in N. side) #7
 9" Maple S36°W 58.47' (60d spike in W. side) #6
 3" Maple N42°E 42.83' (Center of Tree)
 5" Maple N25°E 73.85' (60d spike in N.W. side) #8

Signed by Robert L. Wetherell
 Surveyor's Michigan License No. 24624

Date NOV 9, 1999

