

**SURVEY &
REMONUMENTATION**

JUN 0 9 1997

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in

Osceola

(County)

Located in:

Corner Code #

1. Public Land Survey	T	18N	R	3W	K-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
24 April 1997

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung, in a field survey on 08-14, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor Orson Lyon on 6 January 1848. Set wood post 80.00 chains from the South.

Beech 12" S47W 55 lks.

Beech 13" N61E 42 lks.

From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" X 1" X 20" long bolt, 3 feet South of Centerline in East and West Road and 6 feet West of centerline of road South., 4" below surface. Excavated to 43" and found no other evidence. Placed Osceola County Monument in position of bolt 6" below road surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner K-11. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.

NE Corner Block Garage S44W 71.20 feet. O.B.P.

14" R. Pine N14E 41.65 feet.

Power Pole S24E 74.90 feet.

10" W. Pine S42W 56.80 feet.

Signed by *Matthew McClung*
Surveyor's Michigan License No. 13037

Date April 14, 1997



thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a 1/2" iron bars were added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been entered in the County Surveyors records.

I have shown 2 PA 132 survey; Liber 369, Page 594; Liber 34, Page 118.

I have shown 3 LCRC; Liber 2, Page 22; Liber 2, Page 23; Liber 2, Page 140.

Osceola Township Book, Pages 60 and 61.

SURVEY &
REMONUMENTATION

JUN 09 1997

COMMISSION

OSCEOLA COUNTY
REGISTER OF DEEDS

97 APR 30 PM 12:32

Harvey Crawford

13