

JUN 9 1987

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMERCIAL

Osceola

(County)

Located in:

Corner Code #

- 1. Public Land Survey T 18 N R3 W L-12
 T ___ R ___ _____
 T ___ R ___ _____
 T ___ R ___ _____
- 2. Property Controlling S ___ T ___ R ___ _____
 in Section S ___ T ___ R ___ _____
- 3. Miscellaneous S ___ T ___ R ___ _____
 Property in Sec. S ___ T ___ R ___ _____

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
24 April 1997

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Matthew McClung, in a field survey on 08-14, 19 1996 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35				
13													

A. Description of original monument and accessories and/or subsequent restoration:

I have shown 2 PA 132 surveys; Liber 580, Page 383-385; Liber 586, Page 614

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set Osceola County Monument 6" below surface on line between North and South 1/4 Corners, using distance from Wetherell Survey, Corner is 7' West of centerline of North and South Road and 4' South of fence rows East and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner L-12. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.
12" Elm S36W 29.40 feet.
W. End 14" CMP S80W 13.35 feet.
6" Ash S48W 66.62 feet
21" Walnut N10E 204.35 feet.

Signed by Matthew McClung
Surveyor's Michigan License No. 13037

Date April 14, 1997



Matthew McClung
97 APR 30 PM 12:32
OSCEOLA COUNTY
REGISTER OF DEEDS