

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Osceola Located In _____ Corner Code # _____
(County)

1. Public Land Survey T _____ R _____
T _____ R _____

2. Property Controlling in Section S 19 T 18N R 8W 8
S 19 T 18N R 8W 15

3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Sept. 7, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

8 - None

15 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

8 - CW 1/16 Cor., Sec. 19 - Set stamped 2" Aluminum cap on 5/8" x 34" rebar per standard BLM procedure. Corner of a single strand S & E is 6'± S and 22'±W.

15 - W 1/16 Corner common to Sec. 19 & 30 - Set stamped 2" Aluminum cap on 5/8" x 34" rebar per standard BLM procedure. Falls in remains of down E-W woven wire fence. E-W single strand is 4.5' North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8 - Stamped 2" Aluminum Cap on 5/8" x 34" rebar.
S70°W 22.74' to set Nail and Tag in South side 23" Red Oak
N25°W 35.77' to set Nail and Tag in Northeast side
6" Red Maple
N48°E 58.21' to set Nail and Tag in Northwest side
15" Red Maple
S30°E 9.43' to set Nail and Tag in Southwest side 13" Beech
Set Blue Carsonite Post with Location Tag 1' Southwest

15 - Stamped 2" Aluminum Cap on 5/8" x 34" rebar.
Blue Carsonite Post with Location Tag 1' Northwest
N20°W 21.62' to set Nail and Tag in West side
12" Sugar Maple
N66°W 36.01' to set Nail and Tag in Northeast side
Tri. 18" Sugar Maple
N40°E 29.11' to set Nail and Tag in Southeast side
9" Sugar Maple
S55°E 43.61' to chiseled 'X' on top West side of a 3.5' x 3' x 2' Boulder

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 10/2/2007