

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---------------------------------------|------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 18 N. R. 9 W. | J-13; K-13 |
| 2. PROPERTY CONTROLLING IN SECTION 35 | T. 18 N. R. 9 W. | 16 |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. N. R. E. W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 25, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- J-13** Found 1½" pipe in tile mon. which we conclude to be a Temple restoration of the south township boundary. No U.S. evidence.
 - K-13** Found tile mon. which we conclude to be the standard corner as restored in a Temple survey of the south township boundary.
 - 16** Set by standard survey procedure for the subdivision of sections

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| J-13 | K-13 | 16 |
|--|--|---|
| Set DNR mon. beside tile mon. and cedar post | Set DNR mon. at tile mon. and cedar post | Set 5/8 bar w/RLS cap and cedar post w/loc. tag |
| 2" R. Oak N25°W 41.0 | 5" Maple N20°E 39.9 | 11" Cherry N40°E 49.1 |
| 6" Maple N70°E 30.4 | 3" Maple N85°W 22.3 | 20" R. Oak N70°E 90.5 |
| E-W random Due N 5.3 | NE Sec. 2 T17N-R9W | E-W random Due N 2.6 |
| N¼ Sec. 2 T17N-R9W | Due E 24.4 | E 1/16 on N line Sec. 2 |
| Due E 20.9 | | T17N-R9W Due E 22.6 |

SIGNED BY Kenneth J. Ostling DATE 12-16

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CEDAR TOWNSHIP
OSCEOLA COUNTY