

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 18 N. R. 9 W.	L-11; M-11
2. PROPERTY CONTROLLING IN SECTION _____	25, T. 18 N. R. 9 W.	1; 4
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 23, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument, unless necessary and for subsequent restoration~~

C. (continued)

4
Set 5/8"x40" rod w/RLS cap
& cedar post
1" R. Pine N35°W 33.9
3" R. Oak S70°W 26.0
6" Maple N75°W 75.6

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-11 Set corner by proportionate measurement, midpoint on line, between section corners.
Could locate no previous corner.
- L-11 Found 1/2" pipe in tiles at corner probably as restored by TEmple in previous survey of townline.
- 1 Set by standard survey procedure for subdivision of sections.
- 4 Set by standard survey procedure for subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11	M-11	1
Set 5/8"x40" rod w/RLS cap in ctr. E-W gravel road	Left 1/2" pipe in tile monument in place	Set 5/8"x40" rod w/RLS cap & cedar post in old N-S fn. line
13" Twn.R. Oak N55°E 49.2	3" W. Oak N35°W 31.8	13" W. Oak N20°W 46.2
9" Twn. Maple S10°E 64.5	4" Cherry N02°E 91.6	3" Maple N80°E 7.9
	Set cedar post w/loc. tag N45°W 47'	12" Twn. Maple S05°E 12.7

SIGNED BY Kenneth J. Ostling DATE 10/1/77

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CEDAR TOWNSHIP
OSCEOLA COUNTY