

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 18 N. R. 9 W. ●	I-7; K-12
2. PROPERTY CONTROLLING IN SECTION 35 _____	T. 18 N. R. 9 W. ●	1; 7
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 18, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and subsequent restorations~~

C. (continued)

7

Set 5/8"x40" rod w/RLS cap  
and cedar post  
14" Maple N25°E 36.1  
13" Maple S40°E 40.3  
Old N-S fence Due W 35'  
N-S Trail Due E 130'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
I-7 Found 3/4" iron rod in center E-W road, two McClung BT stump remains in place.

K-12 Set corner by proportionate measurement, midpoint on line, between section corners. No evidence of a previous corner.

1 Set by standard survey procedure for the subdivision of sections.


7 Set corner by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p style="text-align: center;">I-7</p> <p>Fd. 3/4" round iron in ctr. E-W road</p> <p>7" Cherry N40°W 43.4</p> <p>4" W. Pine N60°E 56.2</p> <p>5" Maple Due S 27.6</p> <p>Set cedar post w/loc. tag Due N 33'</p>	<p style="text-align: center;">K-12</p> <p>Set DNR mon. &amp; cedar post</p> <p>6" Maple N60°W 5.6</p> <p>15" W. Pine S20°E 71.2</p> <p>8" Maple S15°W 29.3</p> <p>Ctr. old RR grade SE &amp; NW Due E 5'</p>	<p style="text-align: center;">1</p> <p>Set 5/8"x37" rod w/RLS cap</p> <p>11" Maple N30°E 29.6</p> <p>3" Maple in clump S20°E 48.2</p> <p>Ctr. E-W Rd. Due S 8'</p> <p>Set cedar post w/loc. tag Due S 33'</p> <p>Approx. ctr. 4'x6' Rock 13'</p>
---	---	---

SIGNED BY Kenneth J. Ostling DATE 12/1

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ CEDAR TOWNSHIP OSCEOLA COUNTY