

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Osceola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>9W</u>	<u>F-1</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on July 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5			4		3		2		1	
3												
4	7	8			9		10		11		12	
5												
6	10	17			16		15		14		13	
7												
8	19	20			21		22		23		24	
9												
10	30	29			28		27		26		25	
11												
12	31	32			33		34		35		36	
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1 - Not set in original GLO survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 - Closing 1/4 Corner common to Sec. 4, T18N,R9W. Set 4" DNR Alum. Cap in 1' of 4" PVC w/ Concrete, on 1"x 36" Galv. Iron Pipe, midway between E-1, T18N,R9W & G-1, T18N,R9W on the Standard line. Monument is in WSW-ENE sand Rd. in line w/ old E-W fence remains. Monument accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 - 4" DNR Alum. Cap in 1' of 4" PVC w/ Concrete, on 1"x 36" Galv. Iron Pipe with ring of stone - down 0.5'  
 East 43.33' to F-13, T19N, R9W  
 N27°W 47.11' to N&T in NW. Side 3" R. Pine  
 S78°W 84.48' to N&T in N. Side 9" R. Oak - scribed 'CCBT'  
 S13°W 50.96' to N&T in E. Side 9" R. Oak - scribed 'CCBT'  
 N2°W 39.91' to N&T in E. Side Tw. 4" W. Oak  
 Set blue Carsonite post 15' S.



Signed by Craig W. McVean  
 Surveyor's Michigan License No. 39088

Date 10/19/1998