

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Osceola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>9W</u>	<u>F3</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____



4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on April, 8 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3						●							
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- F-3 -GLO- Set 1/4 Post-J. Hodgson-1838
Maple 8" S10°E 23L., Maple 9" S63°W 13L.
- Osceola Co. Cedar FB., P.16-17 -1904, Partial Sur. of Sec. 4
Pine 36" S49°E 73L., Pine 18" N11°E 109L.
- Swiss Alpine #3 -L. X of Plats, P. 285-291 -F.J. Berning-1975
Conc. Mon.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3- 1/4 cor. common to Sec. 4 & 9 - Found old 1/4"x2.5"x21" long iron sleigh runner in ring of stone. Iron was loose and only 8" in ground. No Conc. Mon was found. This being the NW cor. of Swiss Alpine #3 plat we find nearest iron lot corners 30.93'(P&M) S and 242.42'(P&M) E to establish corner position. Set 4" DNR A.C. on 1"x 36" iron pipe in found ring of stone within 0.2' of loose iron runner per record plat irons. Find remains of both Co. Surveyor BT Stps. in agreement with this position. Reset iron sleigh runner on N side as memorial. This position is believed to have been perpetuated by Co. Surveyor F. Trumbull in the 1904 and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-3 - Set 4" alum. Cap-Edge pond 8' +/- W.
- Added more stones and Carsonite guard post
- S49°E 48.77' to set spike in CL.36" ± Pine Stp. remains (Old NBT)
- N11°E 71.86' to set spike in CL.16" Pine Stp. remains (Old NBT)
- N10°W 142.68' to set N&T in W side 4" R. Oak scribed 'XBT'
- N75°E 36.17' to set N&T in S side 5" R. Maple scribed 'XBT'
- S37°E 51.98' to set N&T in NE side 10" B. Cherry scribed 'XBT'
- S 68°E 53.48' to set N&T in NW side 8" Tw. R. Maple-Fnd. blazed
- S27°W 15.66' to set N&T in NW side 12" R. Maple scribed 'XBT'



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 10/19/1998