

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Osceola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>9W</u>	<u>G-1</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on Oct. 20 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		11		12		13		14		15		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1 - GLO - intersect North Bdy. 30 links West of Post
 Set post at intersection - J. Hodgson - 1838
 Beech 7" S16°E 20L.
 Beech 14" S40°W 54L.
 - A.O. Temple - 1892 - FND. Stp. of Closing Corner
 for 3-18-9 with hack mark and placed
 (G13-T19N, R9W) according to field
 notes. Set Tile Mon. with 4' Iron(at G13)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 - Closing Corner Common to Sec. 3 & 4, T18N, R9W - Found Temple tile monument at G-13, T19N, R9W.
 Set 4" DNR A.C. on 1" x 36" Iron Pipe by prorating GLO closing distance per BLM procedure and placing on Standard Line. Monument accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 - 4" DNR Alum.Cap on 1" x 36" Iron Pipe - Leans N. to clear large boulder below.
 Built Ring of Stone. Blue Carsonite Post Set 1'S.
 East 19.57' to G13 - T19N, R9W
 N8°E 3.59' to N&T in E. Side 3" R. Oak
 N38°W 37.45' to N&T in NE Side 4" R. Oak
 N84°W 33.42' to N&T in S Side Tw. 24" R.Oak
 S19°W 15.25' to N&T in W. Side 6" R. Oak scribed "CCBT"



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 10/14/1998