

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Osceola Located In: Corner Code #  
 (County)

1. Public Land Survey T 18N R 9W H-4  
 T \_\_\_\_\_ R \_\_\_\_\_  
 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on Oct. 19 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-4 - M. McClung 1970 field notes.  
 Fnd. 2" Gas Pipe 2558.81' N. of S1/4 (H-5)

- Rec. Survey. L. 470, P. 740 Matt McClung - 1987  
 Set 5/8" steel rod.  
 10" W. Oak S45°E 16.90'  
 12" W. Oak N30°W 24.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-4 - C 1/4, Sec. 10, T18N, R9W. Fnd. P.S. Cap #13037 on 5/8" x 18" iron rod per Record Survey. Fits line between H-3 & H-5 well and McClung distance S. to H-5. Latitudinal position is open to interpretation due to G4 being in a Lake. Monument accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-4 - Replaced capped 5/8" Iron rod with 4" DNR Alum. Cap on 1" x 36" long Galv. Iron pipe. Built ring of stone  
 S 17° E 18.71' to N&T in W. side Tw. 11" R. Oak  
 N 86° E 40.88' to N&T in S. side Tw. 12" R. Maple  
 N 42° E 28.34' to N&T in NW. side Tw. 21" R. Oak - scribed 'XBT'  
 S 82° W 11.15' to N&T in N. side 4" R. Maple - scribed 'XBT'  
 S47°E 16.87' to set N&T in NE side 8" W. Oak (MM)  
 S60°W 24.44' to set N&T in N. side 8" W. Oak (MM?)  
 Fnd. Steel post 0.9' E.  
 Set blue Carsonite post 1' NE.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		●		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													



Signed by Craig W. McVean Date 12/9/1998  
 Surveyor's Michigan License No. 39088