

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Osceola Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 18N R 9W \_\_\_\_\_ I-1 \_\_\_\_\_  
 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on Dec. 4 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-1 - GLO - Intersect 55L West of Post - Set post - J. Hodgson - 1838  
 Maple 8" S54°E 36L  
 Pine 12" S63°W 13L  
 -A.O. Temple - 1892 - (Set Tile Mon. at I-13, T19N, R9W)  
 Stump of Maple 7" N19°W 17L, (OBT to Standard Corner) and placed stake 53L E. of Cor. to the corner of T18N, R9W, finding that corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 - Closing Corner common to Sec. 2&3, T18N, R9W. Set 4" DNR Alum. Cap on 1"x36" Galv. Iron Pipe on standard line per record Temple closing distance of 53L, (55L GLO), West of found Tile Mon. @ I-13, T19N, R9W. CL. N-S Sand Rd. is 14' E. Dug S63°W 9' and found remains of Pine wood at GLO Pine BT location. Monument accepted as a careful & faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 - 4" Alum. Cap on 1"x36" Iron Pipe. Built ring of stone. Set blue Carsonite Post 1' S.  
 East 34.98' to I-13, T19N, R9W.  
 S56°W 9.84' to N&T in NW. Side 4" R. Oak  
 S24°E 9.10' to N&T in W. Side 6" W. Oak - scribed 'CCBT'  
 S80°E 30.22' to N&T in S. Side 4" W. Pine  
 S24°W 29.02' to set N&T in W. Side 6" W. Pine - scribed 'CCBT'

Register of Deeds Stamp & File Num.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Craig W. McVean  
 Surveyor's Michigan License No. \_\_\_\_\_ 39088

Date 10/14/1998