

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Osceola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 18N R 9W	I-2
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on April 9, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	5		5		4		3		●	2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-2 - GLO - Set post. J. Hodgson - 1838  
 Pine 16" S81°E 13L.  
 Beech 7" S37°W 22L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-2 - 1/4 Corner common to Sec.'s 2 & 3, T18N, R9W. Fnd remains of apparent GLO Pine, (stump to ground) and measured GLO distance to establish corner. Position of corner falls in old down N-S fence. We find end of wire loop lying near here and large stone with anchor wire 5' ± N. Position fits N-S single proportion distance very close and is 9' ± W. of straight line between I-1 & I-3. Set 4" DNR A.C. on 1" x 3' long galv. iron pipe. Monument accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2 - 4" DNR Alum.Cap on 1" x 3" galv. iron pipe in ring of stone.  
 S81°E 9.25' to set cabin spike in centerline remains 16" ± W. Pine stp.  
 N77°W 43.88' to 5/8" x 3/4" rebar in centerline remains 36" W. Pine stp.  
 N12°W 45.75' to Set N&T in W. Side 3" R. Maple - scribed 'XBT'  
 S38°W 35.68' to Set N&T in SE Side 2" R. Oak  
 S16°W 27.35' to Set N&T in E. Side 2" R. Oak  
 Set Blue Carsonite post 1.5' N.



Signed by Craig W. McVean  
 Surveyor's Michigan License No. 39088

Date 10/14/1998