

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Osceola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 18N R 9W	K-1
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on Dec. 4, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5			4		3		2		1	
3												
4	7	8			9		10		11		12	
5												
6	16	17			16		15		14		13	
7												
8	19	20			21		22		23		24	
9												
10	30	29			28		27		26		25	
11												
12	31	32			33		34		35		36	
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1 - GLO - N. Bd'y. 45L W. of Post. Set Post at Intersection - J. Hodgson - 1838  
 Beech 9" S15°W 9L  
 Beech 7" S61°E 31L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 - Closing Corner common to Sec. 1&2, T18N,R9W. FND. Iron & Tile Monument @ K-13, T19W,R9W, Being an original perpetuation of the Standard Corner by A.O. Temple in 1892. Set 4" DNR Alum. Cap On 1"x36" Galv. Iron Pipe by prorating Closing Distance to Standard Line Distance per BLM procedure. Monument accepted as a careful & faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 - 4" DNR Alum. Cap on 1"x36" Iron Pipe in Ring of Stone.  
 Set blue Carsonite post 1' S.  
 East 29.44' to K-13, T19N,R9W.  
 S80°E 9.87' to N&T in S. Side 3" R. Oak - scribed 'CCBT'  
 S11°E 15.70' to N&T in W. Side 4" R. Oak - scribed 'CCBT'  
 N25°E 31.93' to N&T in NW. Side 4" W. Oak - scribed 'CCBT'  
 N30°W 28.09' to N&T in W. Side 3" W. Oak.



Signed by Craig W. McVean  
 Surveyor's Michigan License No. 39088

Date 10/14/1998