

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Osceola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>9W</u>	<u>L-7</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on June 16, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-7 -GLO - Set 1/4 Post - J. Hodgson - 1838
 Beech 8" S66°E 23L
 Beech 9" N46°W 27L
- LCRC L.2, P.7 - K.J. Ostling - 1977
 Set Department of Natural Resources Monument
 by proportion E&W and 33' N of E-W fence. Old
 NBT face corner.
 14" Maple S10°E 36.5'
 8" R. Oak S75°W 37.3'
 48" WPS S80°E 19.8' (Old NBT)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7 - 1/4 corner common to sections 13 and 24. Found 4"
 Department of Natural Resources Alum.Cap on 1" Pipe
 in ring of stone per Rec. LCRC. Monument accepted as
 the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-7 - DNR Monument . Added stones and Carsonite post 1' N.
 6" cedar post 1' SE
- * S73°W 37.67' to set N&T in N side 11" R. Oak (KJO)
- * N17°W 19.75' to set N&T in W side 2" W. Oak
- * N26°E 25.22' to set N&T in NW side 4" R. Oak
- * S74°E 52.20' to set N&T in S side 14" R. Maple
- * Note: BT's scribed "XBT"



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 10/15/1998