

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Osceola
(County)

Located In: 18N 9W Corner Code # B-7

- | | | | | | |
|------------------------------------|---|-------|---|-------|-------|
| 1. Public Land Survey | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew A. McClung
August 3, 1995

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Matthew McClung July 28, 1995

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor John Hodgson on 30 Jan. 1838. Set wood post 33.75 chains from West.
 Sugar 18" S22W 14 lks.
 Sugar 16" N32E 10 lks.

The corner was recorded in Cedar Twp. Book on pages 4 and 5.

I have shown 1 PA 132 survey by Salisbury.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" bar 3" below Road surface. Found 3 chips of crockery at top of bar. Bar was bent on top 3" to East. Excavated to 17" and removed bar. Bar was 25" long and came to very sharp point, placed Osceola County Monument in position of bar. Fence line North and South from Corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner B-7. Osceola County Monument, which is a 3" brass cap mounted on 1" pipe 18" in length.
 East most of three 14" Cherry N45W 53.1 feet.
 5" White Ash N40W 52.25 feet.
 24" Maple N03E 34.1 feet.
 Corner Fence Post South 32.7 feet: O.B.P.

Found 3 Salisbury witnesses

Janey Campbell
OSCEOLA COUNTY REGISTER OF DEEDS
95 AUG -9 PM12:13

Signed by *Matthew McClung* Date July 28, 1995
 Surveyor's Michigan License No. 13037

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983