

FF

1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Commission

Osceola  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 18R 9W      C-5  
    T             \_\_\_\_\_  
    T             \_\_\_\_\_  
    T             \_\_\_\_\_
- 2. Property Controlling    S             \_\_\_\_\_  
    in Section                S             \_\_\_\_\_
- 3. Miscellaneous            S             \_\_\_\_\_  
    Property in Sec.         S             \_\_\_\_\_

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County  
*Matthew M. McClung*  
7 Nov 1996

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Matthew McClung, in a field survey on 10-7, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor John Hodgson on 10 June 1838. Set wood post 80.00 chains from South.  
Tamarack 12" N21E 10 lks.  
Pine 10" S50W 25 lks.

Cedar Township Book; Pages 20 and 21, Pages 52 and 53.

I have shown 2 L.C.R.C: Liber 2, Page 362 and Liber 3 Page 118.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe drove into old road in monument box 27" below present road surface. Placed Osceola County Monument over position of 3/4" pipe in monument box. Corner is in centerline of North and South, East and West roads.

OSCEOLA COUNTY  
REGISTER OF DEEDS  
NOV 26 PM 2:14  
*Matthew McClung*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C-5 . Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 30" in length.  
Power Pole w/nail S68E 87.2 feet.  
Eye of East Gye Wire S58E 65.40 feet.  
S. End of Culvert S52W 39.15 feet.  
S. End of Culvert S56E 43.65 feet.



Signed by *Matthew M. McClung*  
Surveyor's Michigan License No. 13037

Date pt. 21, 1996