

**SURVEY & REMONUMENTATION**

DEC 13 2000

**LAND CORNER RECORDATION CERTIFICATE**

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

**SECTION**

For corners in <u>Osceola</u>	Located in:	Corner Code#
1. Public Land Survey	<u>T 18 W</u> <u>R 9W</u>	<u>F-9</u>
	<u>T</u> <u>R</u>	_____
	<u>T</u> <u>R</u>	_____
	<u>T</u> <u>R</u>	_____
2. Property Controlling in Section	<u>S</u> <u>T</u> <u>R</u>	_____
	<u>S</u> <u>T</u> <u>R</u>	_____
3. Miscellaneous Property in Sec.	<u>S</u> <u>T</u> <u>R</u>	_____
	<u>S</u> <u>T</u> <u>R</u>	_____
4. Lot No. _____ Recorded Plat _____		
5. Private Claims _____		

OSCEOLA COUNTY  
 REGISTER OF DEEDS  
 00 OCT 11 AM 9:49  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on May 16, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**F-9 - 1/4 Corner common to Sections 21 & 28, T18N, R9W**

**A. Description of original monument and accessories and/or subsequent restoration:**

**1838 - J. Hodgson, G.L.O.**  
 "Corner is a 14" Hemlock"  
Undated from Co. Surveyors Twp. Notes  
Pages 5 & 59  
 "Gun Barrel"  
 #1 - 40" Pine N70°E 3 1/2 feet  
 #2 - 40" Pine N15°W 22 1/2 feet  
 #3 - Distance West = 2647.7'

**1978 - R.L. Wetherell, LS 24624**  
 L.C.R.C. - Liber 02, Pg. 60.  
 Found Gun Barrel with Pine Stump  
 N70°E 4 feet. Replaced with Concrete Monument.  
 #4 - 12" Maple West 55.76'  
 #5 - 8" Maple N44°W 57.51'  
 #6 - 4" Maple N6°W 20.95'  
 #7 - 6" Maple S42°E 53.74'

**B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:**

I found the 4" x 36" Concrete Monument I placed in 1978.


Condition of the accessories are as follows: #1 Found stump, #2 Gone, #3 Measured 2642.5', #4 Found in good condition, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I accepted the 4" x 36" Concrete Monument as a substantial marker for the corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 9" Tw. Maple S44°E 33.63' (60d spike E. side) #7
- 10" Maple N6°W 21.22' (60d spike N.W. side) #6
- 16" Maple N82°W 55.90' (60d spike N. side) #4
- 12" Maple N44°W 57.76' (60d spike N.E. side) #5
- 14" R. Oak S59°W 82.00' (60d spike N. side)

APPROVED LAND CORNER  
 P.A. 345 OF 1990  
 Osceola County  
R.L.W.  
8-17-00



Signed by Robert L. Wetherell  
 Surveyor's Michigan License No. 24624

Date August 22, 2000

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN. 1983  
 ADAPTED FOR WORD PROCESSING JANUARY, 1999