

**SURVEY &  
REMONUMENTATION**

**FEB 12 1998**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

<u>Osceola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>9W</u>	<u>F-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County  
*16 Oct. 1997*  
*Matthew McClung*  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Matthew McClung, in a field survey on Sept 12, 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
The original corner was set by deputy surveyor John Hodgson on 21 November 1837. Set wood post 40.00 chains from East.  
Hemlock 8" N49E 21 Lks.  
Beech 7" N7W 11 Lks  
Found Tile and iron for North One Quarter Corner of Section 4, T17N-R9W.  
Non recorded survey by Cole  
of Section 4, T17N-R9W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Hired Backhoe and excavated area west of tile corner, 3 feet deep and found no evidence of corner. Placed Osceola County Monument 6.93 feet West of found Tile Corner (average G.L.O. distance).

*James Crawford*  
97 NOV 26 AM 11:47  
OSCEOLA COUNTY  
REGISTER OF DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner F-13. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.  
24" Maple S46E 43.30 feet.  
24" Maple S63E 70.30 feet.  
12" R. Oak S46W 29.93 feet.  
8" R. Pine S18W 40.40 feet.



Signed by *Matthew McClung*  
Surveyor's Michigan License No. 13037

Date Sept. 21, 1996