

**SURVEY &
REMONUMENTATION**

NOV 16 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

<u>Osceola</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 18N R 9W	G-1
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew M. [Signature]
23 July 98

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on Oct. 20 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1 - GLO - intersect North Bdy. 30 links West of Post
Set post at intersection - J. Hodgson - 1838
Beech 7" S16°E 20L.
Beech 14" S40°W 54L.
- A.O. Temple - 1892 - FND. Stp. of Closing Corner
for 3-18-9 with hack mark and placed
(G13-T19N, R9W) according to field
notes. Set Tile Mon. with 4' Iron(at G13)

Nancy [Signature]
98 OCT 21 PM 4: 12
OSCEOLA COUNTY
REGISTER OF DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 - Closing Corner Common to Sec. 3 & 4, T18N, R9W - Found Temple tile monument at G-13, T19N, R9W.
Set 4" DNR A.C. on 1" x 36" Iron Pipe by prorating GLO closing distance per BLM procedure and placing on Standard Line. Monument accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 - 4" DNR Alum.Cap on 1" x 36" Iron Pipe - Leans N. to clear large boulder below.
Built Ring of Stone. Blue Carsonite Post Set 1'S.
East 19.57' to G13 - T19N, R9W
N8°E 3.59' to N&T in E. Side 3" R. Oak
N38°W 37.45' to N&T in NE Side 4" R. Oak
N84°W 33.42' to N&T in S Side Tw. 24" R.Oak
S19°W 15.25' to N&T in W. Side 6" R. Oak scribed "CCBT"



Signed by Craig W. McVean
Surveyor's Michigan License No. 39088

Date 10/14/1998

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1995