

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Osceola
(County)

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>18N</u> R <u>9W</u> | <u>G-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

December 14 1994
Matthew A. McClung

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Matthew McClung, in a field survey on November 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor John Hodgson on 10 June 1838. Set wood post 80.00 chains from South.
 Beech 8" S61E 60 lks.
 Beech 14" N62W 48 lks.
 LCRC recording, Lib. 3, page 67 by Fokens.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rod 3" below surface, and plow point lying on surface. Also D.N.R. Witness post next to rod. No cap was on rod.

OSCEOLA COUNTY
 REGISTER OF DEEDS
 95 APR 10 PM 2:37
Nancy Crawford



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G-11. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 30" in length.
 Telephone pedestal N17E 26.15 feet. O.B.P.
 Nail & L.S.C. tag in North face 8" Beech N50W 26.2 feet O.B.T.
 Nail and tag NE face 30" W. Oak S40W 36.20 feet. O.B.T.
 30" R. Oak N45W 11.65 feet (20 penny spike)

Signed by Matthew McClung Date November 28, 1994
 Surveyor's Michigan License No. 13037