

Aug 15 1999

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Osceola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 18N R 9W	H-1
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County

*Matthew McCamp*  
6 Aug 1999

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on July 28, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

*Matthew McCamp*  
98 DEC 17 PM 2:01  
OSCEOLA COUNTY  
REGISTER OF DEEDS

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-1 - Not set in original GLO survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1 - Closing 1/4 Corner common to Sec. 3, T18N,R9W. Set 4" DNR Alum. Cap on 1"x 36" Galv. Iron Pipe, midway between G-1, T18N,R9W & I-1, T18N,R9W on the Standard line. Monument is in bottom, S. end, of bowl area, open to the North. Monument accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1 - 4" DNR Alum. Cap on 1'x 36" Galv. Iron Pipe in ring of stone  
East 25.23' to H-13, T19N,R9W  
S70°W 65.47' to N&T in N. Side 14" R. Maple - scribed 'CCBT'  
S22°E 17.15' to N&T in E. Side 4" R. Maple - scribed 'CCBT'  
S71°E 55.07' to N&T in SW. Side 4" B. Cherry  
Set blue Carsonite post 1' S.



Signed by *Craig W. McVean*  
Surveyor's Michigan License No. 39088

Date 10/14/1998