

**SURVEY &  
REMONUMENTATION**

APR 25 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Osceola  
(County)

Located In:

Corner Code ##

- |                                    |                          |             |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey              | T <u>18N</u> R <u>9W</u> | <u>H-11</u> |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County

*29 Nov. 1994*  
*Matthew McClung*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Matthew McClung, in a field survey on November 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor John Hodgson on 10 June 1838. Set wood post 40.05 chains from East.  
Beech 7" S62E 38 lks.  
Elm 10" N28W 13 lks.  
2 LCRC recordings, Lib. 2, page 8 (Ostling) Liber 3, page 67 Fokens.  
2 Act 132 recordings, Lib. 366, Page 493 and Lib. 400, page 69.  
Page 18 of Township Book.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rod, and plow point 3" below Road surface. Placed Osceola County Monument over 5/8" rod 6" below road surface. Cap was gone from rod and rod was bent 3" to west.

OSCEOLA COUNTY  
REGISTER OF DEEDS

94 DEC -7 PM 2:52

*Nancy Crawford*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H-11. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.  
D.N.,R. Cedar witness post North 33.0 feet.  
4" Maple (soft) S35E 35.2 feet. O.B.T.  
6" S. Maple S30W 43.7 feet. O.B.T.  
14" S. Maple N45E 41.75 feet. O.B.T.

Signed by Matthew McClung

Date November 28, 1994

Surveyor's Michigan License No. 13037