

**SURVEY &
REMONUMENTATION**

NOV 16 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McVean
23 July 98

SECTION
For corners in

Osceola (County) Located in: Corner Code #

1. Public Land Survey T 18N R 9W I-1
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

Register of Deeds Stamp & File Num

4. Lot No. , Recorded Plat

5. Private Claims

I, Craig W. McVean, in a field survey on Dec. 4 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1 - GLO - Intersect 55L West of Post -Set post - J. Hodgson - 1838
 Maple 8" S54°E 36L
 Pine 12" S63°W 13L
 -A.O. Temple - 1892 - (Set Tile Mon. at I-13, T19N, R9W)
 Stump of Maple 7" N19°W 17L, (OBT to Standard Corner) and placed stake 53L E. of Cor. to the corner of T18N, R9W, finding that corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 - Closing Corner common to Sec. 2&3, T18N, R9W. Set 4" DNR Alum. Cap on 1"x36" Galv. Iron Pipe on standard line per record Temple closing distance of 53L, (55L GLO), West of found Tile Mon. @ I-13, T19N, R9W. CL. N-S Sand Rd. is 14' E. Dug S63°W 9' and found remains of Pine wood at GLO Pine BT location. Monument accepted as a careful & faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 - 4" Alum. Cap on 1"x36" Iron Pipe. Built ring of stone. Set blue Carsonite Post 1' S.
 East 34.98' to I-13, T19N, R9W.
 S56°W 9.84' to N&T in NW. Side 4" R. Oak
 S24°E 9.10' to N&T in W. Side 6" W. Oak - scribed 'CCBT'
 S80°E 30.22' to N&T in S. Side 4" W. Pine
 S24°W 29.02' to set N&T in W. Side 6" W. Pine - scribed 'CCBT'



OSCEOLA COUNTY
REGISTER OF DEEDS

98 OCT 21 PM 4:12

Signed by Craig W. McVean Nancy Crawford
 Surveyor's Michigan License No. 39088

Date 10/14/1998