

FEB 13 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola (County)	Located In:	Corner Code #
1. Public Land Survey	T 18N R 9W	L-7
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County

*Matthew M. Chung*  
6 Aug 1998

Register of Deeds Stamp & File Num

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Craig W. McVean, in a field survey on June 16, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-7 -GLO - Set 1/4 Post - J. Hodgson - 1838  
Beech 8" S66°E 23L  
Beech 9" N46°W 27L
- LCRC L.2, P.7 - K.J. Ostling - 1977  
Set Department of Natural Resources Monument by proportion E&W and 33' N of E-W fence. Old NBT face corner.  
14" Maple S10°E 36.5'  
8" R. Oak S75°W 37.3'  
48" WPS S80°E 19.8' (Old NBT)

*Craig W. McVean*  
98 DEC 17 PH 2:02  
OSCEOLA COUNTY  
REGISTER OF DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-7 - 1/4 corner common to sections 13 and 24. Found 4" Department of Natural Resources Alum.Cap on 1" Pipe in ring of stone per Rec. LCRC. Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-7 - DNR Monument . Added stones and Carsonite post 1' N.  
6" cedar post 1' SE
- \* S73°W 37.67' to set N&T in N side 11" R. Oak (KJO)  
N17°W 19.75' to set N&T in W side 2" W. Oak
- \* N26°E 25.22' to set N&T in NW side 4" R. Oak
- \* S74°E 52.20' to set N&T in S side 14" R. Maple
- \* Note: BT's scribed "XBT"



Signed by Craig W. McVean  
Surveyor's Michigan License No. 39088

Date 10/15/1998