

SURVEY & REMONUMENTATION

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
Osceola
(County)

Located In: _____ Corner Code # _____

- | | | | | |
|------------------------------------|--------------------------|--|--|-------------|
| 1. Public Land Survey | T <u>18N</u> R <u>9W</u> | | | <u>L-11</u> |
| | T _____ R _____ | | | _____ |
| | T _____ R _____ | | | _____ |
| | T _____ R _____ | | | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | | | _____ |
| | S _____ T _____ R _____ | | | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | | | _____ |
| | S _____ T _____ R _____ | | | _____ |

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
29 NOV 1994

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Matthew McClung, in a field survey on November 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor John Hodgson on 7 July 1838. Set wood post 39.78 chains from East.
Beech 16" N27E 49 lks.
Beech 7" N88W 35 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rod, DNR #10068 3 feet North of Centerline of dirt road, 4" below surface. Placed Osceola County Monument over rod, and set monument 6" below road surface.

OSCEOLA COUNTY
REGISTER OF DEEDS

94 DEC -7 PM 2: 52

Nancy Crawford



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner L-11. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.
14" Red Oak S30E 39.65 feet.
North most Clump of 3 R. Oak, 10", S65W 64.25 feet.
14" R. Oak (East of Double) N45E 51.40 feet.
D.N.R. Witness post North 33.0 feet.

Signed by Matthew McClung

Date November 28, 1994

Surveyor's Michigan License No. 13037

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983