

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-------------|---|-------------|------------|
| 1. Public Land Survey | T | <u>18</u> N | R | <u>10</u> W | <u>A-2</u> |
| | T | ___ | R | ___ | ___ |
| | T | ___ | R | ___ | ___ |
| | T | ___ | R | ___ | ___ |
| 2. Property Controlling in Section | S | ___ | T | ___ | R |
| | S | ___ | T | ___ | R |
| 3. Miscellaneous Property in Sec. | S | ___ | T | ___ | R |
| | S | ___ | T | ___ | R |

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

19 Oct 1995
Matthew McClung

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Matthew McClung

October 14, 1995

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor John Hodgson on 26 Nov. 1837. Set wood post 40.00 chains from South.
Beech 14" S23W 26 lks.
Beech 12" N71W 32 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" pipe 2" below surface. Found 6"x6"x6" stone pointed on top 4" below surface. Found flat piece of cast iron 7" below surface. Pipe and Iron were at Southeast of stone 2" from point. Placed Osceola County Monument at position of point on stone and placed stone and cast iron below Monument Cap.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner A-2. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.
2" Red Pine S66W 50.90 feet.
6" Thorn Apple N50W 37.55 feet.
Power Pole N60E 55.00 feet.
5" Elm S14E 84.15 feet.

Nancy Campbell
95 NOV 13 PM 4:52
OSCEOLA COUNTY
REGISTER OF DEEDS

Signed by *Matthew McClung*

Date October 14, 1995

Surveyor's Michigan License No. 13037