

**SURVEY &
REMONUMENTATION**

FEB 16 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Osceola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18R</u> 10W	<u>C-6</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
8 Oct 1998

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung in a field survey on 4-18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
The original corner was set by deputy surveyor John Hodgson on 10 June 1838. Set wood post 40.00 chains from South.
Beech 12" S37W 8 lks.
Beech 7" N66E 16 lks.

Lincoln Township Book (Front pages)
Page 4, Calls for stone & iron
Fence Post East 26.6'
Fence Post West 29'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" X 2" X 1' strap iron 6" below road surface. Excavated to 14" and found another piece of strap iron adjacent to side of 4" X 6" X 10" stone. Placed Osceola County Monument in position of strap iron 6" below surface. Corner is in C/L of N & S road and in fences East & West.

OSCEOLA COUNTY
REGISTER OF DEEDS
98 NOV 23 AM 10:36
James Campbell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C-6. Osceola County Monument, which is a 3" brass cap mounted on 1" pipe 18" in length.
Power Pole N20E 111.5 feet.
24" Cherry West 80.2 feet.
6" Elm N50E 67.6 feet.
3" Cherry N50W 79.2 feet.
Fence row N & S East 26.8 feet.



Signed by *Matthew McClung* Date 23 Nov 98
Surveyor's Michigan License No. 13037