

**SURVEY &
REMONUMENTATION**

FEB 16 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Osceola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>10W</u>	<u>C-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___	_____
	S ___ T ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___	_____
	S ___ T ___	_____



4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung in a field survey on 4-18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
The original corner was set by deputy surveyor John Hodgson on 10 June 1838. Set wood post 80.00 chains from South.
Beech 9" N29W 12 lks.
Beech 9" S61E 32 lks.

Lincoln Township Book (Front pages)
Page 3, Calls for iron.
Elm 6" NE 62.5'.
SW 108.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" rod in center of Monument box 4" below surface. Corner is in centerline of road North and South road and 3' South of centerline of road to East and West.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C-7. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.
Power Pole N50W 107.01 feet.
Old decayed stump S15W 109.45 feet. O.B.T.
4" White Pine S30E 77.2 feet.
Tele. Pedestal S30W 62.05 feet.
24" W. Pine S75W 132.2 feet.

Signed by Matthew McClung 13037
Surveyor's Michigan License No. _____

Date 23 Nov. 98

SURVEY &
REMONUMENTATION

FEB 16 1999

SECTION

OSCEOLA COUNTY
REGISTER OF DEEDS

98 NOV 23 AM 10:36

Nancy Crawford

Act 74, Liber 1, page 218.
Found 1" iron in centerline Rd.
Sign Az 145d- 43.44'.
Set nail & tag NW side 36"
Stump Az 145d- 108.85'.
Set Nail & tag SW side power
pole Az 320d- 42.08'.

Act 74, Liber 2, pages 69 & 70.
Found 1" iron
N45W 42.10' Telephone Pole.
S60E 101.5' 11" Maple.
S25E 91.85' Chris "+" in North
face of gas line marker.