

SURVEY &  
REMONUMENTATION

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola

(County)

Located In:

Corner Code:##

18N 10W

D-1

- |                                    |   |   |       |
|------------------------------------|---|---|-------|
| 1. Public Land Survey              | T | R | _____ |
|                                    | T | R | _____ |
|                                    | T | R | _____ |
|                                    | T | R | _____ |
| 2. Property Controlling in Section | S | T | R     |
|                                    | S | T | R     |
| 3. Miscellaneous Property in Sec.  | S | T | R     |
|                                    | S | T | R     |

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County

*19 Oct. 1995*  
*Matthew McClung*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Matthew McClung

October 14, 1995

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

*Yancy Campbell*  
OSCEOLA COUNTY  
REGISTER OF DEEDS  
95 NOV 13 PM 4:53

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set Corner equal distant from Northeast and Northwest corners of section and on best line of fence line to East. Found fence post, woven wire East and barbed wire West, N58E 4.05 feet. Remains of fence to South is East 36.1 feet. Lincoln Corner is on east slope of cradle knoll. LeRoy Corner is East 12.48 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D-1. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 30" in length.  
22" Maple S13E 47.91 feet.  
4" Maple S78W 18.0 feet.  
9" Spruce SW corner of planting N28W 98.25 feet.  
3" Hemlock S46E 43.90 feet.



Signed by *Matthew McClung*

Date October 14, 1995

Surveyor's Michigan License No. 13037